

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	KSHS.	CTS.
	<b><u>PROPOSED RENOVATION OF AHERO MARKET STALLS IN NYANDO SUB-COUNTY</u></b>					
	<b><u>BILLS OF QUANTITIES</u></b>					
	<b><u>SECTION NO. 2</u></b>					
	<b><u>ELEMENT NO.2</u></b>					
	<b><u>RC SUPERSTRUCTURE</u></b>					
	<u>Concrete Class 20mm in:-</u>					
A	100mm worktop slab	m2	98			
B	Concrete seats	m2	72			
	<b>Provide and fix steel RHS</b>					
C	Size 200mm x 200mm	no	12			
	<b><u>Steel fabric mesh reinforcement to B.S.4483 to slab and concrete seats</u></b>					
D	BRC mesh fabric reinforcement ref A142( weighing 2.2kg/m2) (measured net-no allowance made for lamps)	m2	420			
	<b><u>DOORS</u></b>					
E	Provide and fix steel plate doors complete with fittings	No	71			
	<u>Rainwater Disposal</u>					
F	100mmx150mmx4mm steel gutter	m	116			
	<b><u>Grattings</u></b>					
G	Proved and fix metal gratings to existing drain	m	230			
	<b><u>TOTAL FOR RC SUPERSTRUCTURE CARRIED TO SUMMARY</u></b>					
					-	

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	KSHS.
<b><u>PROPOSED RENOVATION OF AHERO MARKET STALLS IN NYANDO SUB-COUNTY</u></b>					
<b><u>BILLS OF QUANTITIES</u></b>					
<b><u>SECTION NO. 2</u></b>					
<b><u>ELEMENT NO. 5</u></b>					
<b><u>WALLING</u></b>					
<u>Approved local natural stonework; squared and machine dressed;bedded in cement mortar (1:4); reinforced with 25mm wide x 20mm gauge hoop iron strapping every alternate course</u>					
A	200mm Thick dwarf walling	m2	247		
B	150mm Thick dwarf walling	m2	110		
<u>Damp proof course</u>					
C	200mm wide	m	161		
<b><u>TOTAL FOR WALLS CARRIED TO SUMMARY</u></b>					
			<b>KSHS.</b>		

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	KSHS.	CTS.	
	<b><u>PROPOSED RENOVATION OF AHERO MARKET STALLS IN NYANDO SUB-COUNTY</u></b>						
	<b><u>BILLS OF QUANTITIES</u></b>						
	<b><u>SECTION NO. 2</u></b>						
	<b><u>ELEMENT NO. 9</u></b>						
	<b><u>FINISHES</u></b>						
	<b><u>Wall Finishes</u></b>						
	<u>15mm thick Cement and sand (1:4) plaster as described to</u>						
A	Sides of block concrete wall surfaces	m2	416				
B	Sides of slab and soffits	m2	178				
	<u>Prepare and apply two coats of emulsion paint to</u>						
C	Sides of wall surfaces	m2	731				
D	Sides of slab and soffits	m2	178				
	<u>20mm thick screed as described to</u>						
E	Floor	m2	220				
	<b><u>TOTAL FOR FINISHES CARRIED TO SUMMARY</u></b>				<b>KSHS.</b>		

ITEM NO.			SHS.	CTS.
	<p><b><u>PROPOSED RENOVATION OF AHERO MARKET STALLS IN NYANDO SUB-COUNTY</u></b></p> <p><b><u>BILLS OF QUANTITIES</u></b></p> <p><b><u>SECTION NO. 2</u></b></p> <p><b><u>BUILDER'S WORKS</u></b></p> <p><b><u>SUMMARY</u></b></p>	<p><b><u>PAGE NO.</u></b></p>		
1	RC SUPERSTRUCTURE	2/2		
2	WALLING	2/1		
3	FINISHES	2/2		
	<p><b><u>TOTAL FOR MAIN BLOCK CARRIED TO MAIN SUMMARY</u></b></p>	<p><b>KSHS.</b></p>		

ITEM NO.	DESCRIPTION	UNIT	QTY.	KSHS.	CTS.
	<b><u>PROPOSED RENOVATION OF AHERO MARKET STALLS IN NYANDO SUB-COUNTY</u></b>				
	<b><u>BILLS OF QUANTITIES</u></b>				
	<b><u>SECTION NO. 3</u></b>				
	<b><u>MAIN HOUSE</u></b>				
	<b><u>PRIME COST AND PROVISIONAL SUMS</u></b>				
	<b><u>PRIME COST SUMS</u></b>				
A	Allow the Prime Cost Sum of Kenya Shillings One Hundred and Eighty thousand for Contingencies		Sum	180,000	00
B	Allow the Prime Cost Sum of Kenya Shillings One Hundred and Fifty thousand for project management		Sum	150,000	00
C	Allow the Prime Cost Sum of Kenya Shillings Eighty thousand for Demolition works		Sum	80,000	00
D	Allow the Prime Cost Sum of Kenya Shillings Twenty thousand for Dustbins		Sum	20,000	00
E	Allow the Prime Cost Sum of Kenya Shillings Eighty thousand for Tree planters in central square with seating Edges Surround		Sum	80,000	00
F	Allow the Prime Cost Sum of Kenya Shillings Sixty thousand for General Repair to,roof,existing doors etc		Sum	60,000	00
G	Allow the Prime Cost Sum of Kenya Shillings One Hundred a thousand for 4 NO Grile Gate ,size 3000x2600mm for the Entrance		Sum	100,000	00
H	Allow the Prime Cost Sum of Kenya Shillings One Hundred and Fifty thousand for Repair to existing Drainage within the supermarket		Sum	150,000	00
	<b><u>TOTAL FOR PRIME COST AND PROVISIONAL SUMS CARRIED TO SUMMARY</u></b>		<b>KSHS.</b>	<b>820,000</b>	<b>00</b>

ITEM NO.			SHS.	CTS.
	<p><b><u>PROPOSED RENOVATION OF AHERO MARKET STALLS IN NYANDO SUB-COUNTY</u></b></p> <p><u>MAIN SUMMARY</u></p> <p>1. PRELIMINARIES(Signboard and site store)</p> <p>2. BUILDER'S WORKS</p> <p>3. PROVISIONAL SUMS</p> <p>ADD 16% VAT</p> <p><b><u>TOTAL CARRIED TO FORM OF TENDER</u></b></p>	<p><u>PAGE NO.</u></p> <p>1/26</p> <p>2/25</p> <p>3/1</p> <p><b>KSHS.</b></p>		

EMPLOYER:

CONTRACTOR

NAME: .....

NAME: .....

.....

.....

ADDRESS: .....

ADDRESS: .....

.....

.....

SIGNATURE: .....

SIGNATURE: .....

DATE: .....

DATE: .....